

CONSTRUCTION PROJECTS START TO FINISH

From Plans to Patients

August 2024

DISCLOSURES

- I am retiring at the end of the year!



LEARNING OUTCOMES


- Describe rationale for Infection Prevention involvement very early in the project
- Identify key markings on construction drawings
- Utilize patient safety and infection prevention knowledge to address unexpected incidents

WHO AM I?


- RN – 1985
- BS Health Care Leadership – 1999
- Infection Prevention – 2003
- CIC certified 2005, 2010, 2015, 2020
- FAPIC - 2016
- President of local ASHE chapter 2020, 2021, 2024
- Member of the FGI Guidelines 2026 revision team



BARNES-JEWISH HOSPITAL – ST. LOUIS, MO



AND SINCE THE LAST TIME WE SPOKE



QUEENY IS HERE – NOW IT'S GONE



QUEENY IS GONE – NEW TOWER COMING BACK







PROJECT ORGANIZATION AND STAGES

- Feasibility
- Schematic design (SD)
- Design development (DD)
- Construction documents (CD)
- Construction
- Commissioning

FEASIBILITY

- Can this be done?
- Work-flow evaluation
- All rooms
- Ante rooms
- Clean to dirty flow
- Eliminate extra work
- Eliminate non-value-added items (not value engineering)
- Strengths and weaknesses
- Costs

FEASIBILITY

- Does it meet codes and standards
 - AHJ
 - FGI
 - ASHRAE
 - ASHE
 - APIC

FUNCTIONAL PROGRAM

- Owner advises architect of what desired outcome of project is
- Detailed list of interior and exterior spaces required for support of the project
 - Addresses human, technical and building resources necessary
- Architect then starts designing
 - Can all of it fit in the envelope

FUNCTIONAL PROGRAM



BJC HealthCare – BJH

TKH

Barnes Jewish Hospital
Rand Johnson Decant
Hospitalists – Rand Johnson

Project No. 21120-04-00
BJC Project No. 21C707
September 21, 2021 Rev 3.14.2022

Functional Program

Description of Services/Model of Care:

Hospitalists provide care to hospitalized patients at Barnes-Jewish Hospital on both the North and South Campus inpatient units, consult in the Emergency Room, and provide procedures in outpatient areas of the hospital. As part of this patient care, Hospitalists provide education to medical students, interns, and residents through bedside teaching and structured lectures.

Existing and Proposed Location:

Existing: ML Rand Johnson at 5,057 dgsf – relocation required
ML Barnes Administration at 455 dgsf – relocation required
ML Service Bldg. Suites at 2,003 dgsf – planned to remain
ML Peters Building at 652 dgsf – planned to remain
Proposed: TBD

Patient Population:

Local and regional acutely ill patients requiring hospitalization that are admitted through the emergency room to the various medicine designated patient care units/beds on both North and South campus, including Oncology and Bone Marrow Transplant beds on floors 8800 through 12800 in the Parkview Tower.

Current Volumes vs. Projected Volumes (including assumptions):

The Division of Hospital Medicine performs admission services, continuing care visits, discharges, consults, and procedures across the campus, totaling **~110,000 annual visits**. As we discuss further opportunities across the campus, we expect this could **increase year over year by ~5,000 visits**. On average, the service cares for >350 patients per day.

Hours of Operation/Shifts/Visiting Hours:

	Mon.	Tues.	Wed.	Thurs.	Fri.	Sat.	Sun.
Clinical Ops	24/7/365	24/7/365	24/7/365	24/7/365	24/7/365	24/7/365	24/7/365
Admin Ops	7a-6p	7a-6p	7a-6p	7a-6p	7a-6p		

Number of Staff per Shift and Job Descriptions:

Based on Busiest Shift: CURRENT			
Name	Title	Computer Use - % of Shift	Dedicated or Touch-Down?
Departmental Staff			
Information has been omitted with this version of the Functional			



Program – Not Applicable			
Ancillary Staff			
Busiest Shift	# of Dedicated stations needed	# of Touch-down stations needed	
Lightest Shift	# of Dedicated stations needed	# of Touch-down stations needed	
Designed to Typical Shift	# of Dedicated stations needed	# of Touch-down stations needed	

Circulation / Flow:

Patient: N/A

Visitor: Educational, Research, and Professional collaborators/visitors will require daily access.

Nurse: N/A

Physician/Resident: Faculty of the division will require 24/7 access. Residents on service with faculty will also require daily access.

Ancillary Staff (i.e. Dietary, PT, RT, Lab, Pharmacy, Imaging, Etc.): N/A

Materials Management/House Keeping/Materials/Supplies/Soiled: Shred-It – once weekly to any separate area. Housekeeping – 2x per day Mon-Fri, 1x day on weekends.

Key Adjacencies:

Internal: Medicine Units and/or Emergency Department

External:

Communication/Information Systems:

Identify any of the following specialty equipment/software which will be required:

Vocera/Spectralink

Cisco wireless VOIP Phones: Yes

Cell Phone (business use): Yes. All faculty have corporate liable devices.

Video Conferencing: Yes. Division has Vaddio camera/speaker system.

Patient Touch Technology (PTT):

Applications (SIS, Metavision, Provation, Mosaik, Cerner, Dictation, HCLL, etc.):

Require WUSM data lines.

Education or Training Initiatives:

- Simulation Training Room
- Project Rooms to facilitate small group meetings

C:\Users\michaeltch.TKH\AppData\Local\Microsoft\Windows\INetCache\Content.Outlook\Z3J7OJP8\Functional
Program_Hospitalists RGA12.17.21.docx



Anticipated Changes/Trends:

New Services or Expansion of Existing Services

- Anticipate that the clinical footprint of the division will continue to grow year over year. Planning and Identifying space to accommodate, at least, the next decade will be crucial to the space identification criteria.
- Medical Student and Resident Education space needed
- Development of quality improvement program with associated rooms

Changes in Healthcare Delivery or Technology

- Telemedicine
-

Additional Design Criteria/Considerations:

It is critical that the division's primary office suite follows an academic office setting with individual offices for senior faculty and pertinent leaders, as well as a welcoming, professional, and design-affected aesthetic. See: Oncology entry area in MCC. Suitable office space is to be furnished by the Hospital per the master hospitalist agreement. Windows preferred.

Protected Health Information, Human Resource, and Financial data all require secure discussion areas, and are best facilitated by the existence of private offices as several individuals hold different roles that impact these key areas.

This document represents the agreement on the functional information provided by you:	
Sign:	Date:
Sign:	Date:
Administrator:	Date:



Hospitalists
± 10,566 sf
Hospitalists Program:
± 9,145 sf
Program Difference:
± 1,411 sf

Hospitalists Shared Floor Support:

- Cafe / Staff Break
- Conference Rooms
- Work Room

Hospitalists Program TBD:



- Toilet with shower
- Lockers
- Coat Closet

Note: Code Review required.

BJH Mid Campus

MCC - 7th Floor

Concept Test Fit Plan



SCHEMATIC DESIGN (SD)

- Architect consults with owner to determine project goals and requirements
- Architectural program – defines the required functions of the project (functional program)
- Square footage type by usage is determined (offices, patient care, treatment areas etc.)
- Also research phase to make sure all jurisdictional requirements are addressed
- IP input at this phase can prevent design changes later

DESIGN DEVELOPMENT (DD)

- Often specify types of materials used as well as window and door locations
- Things for IP to look for
 - Are fixtures and finishes acceptable
 - Hand washing sinks – number and location
 - ETOH hand rub placement
 - Clean to dirty flow
- Standards document goes with these drawings
- Specifications for everything – established by multi-disciplinary team
 - Beautiful flooring is useless if it can't be cleaned

DESIGN DEVELOPMENT

- Project risk assessment is developed
- IP needs to review fixtures, finishes and materials
- DDs are then presented to owner for review and approval

CONSTRUCTION DOCUMENTS (CD – BID DOCUMENTS)

- Once DDs are approved by all parties architect begins on CDs
- CDs have greater details than DDs
- Specifications are incorporated into the drawings
- Once complete, drawings are sent out for bid
- Design build is very common
 - General contractor is on board from start of DDs
 - General contractor sends out for bids from sub contractors
- IP precautions for dust control are included in these drawings
- Other special IP requirements are also included

Bid Documents



RATAJ-KRUEGER ARCHITECTS, INC.


10777 Sunset Office Dr., Ste. 300, Sunset Hills, MO 63127
(314) 822-4007 www.rkai.net (314) 822-3839 f

Donald J. Rataj NCARB, principal
Kurtis R. Krueger NCARB, principal
Geoffrey L. Crowley AIA, principal


INFECTION PREVENTION NOTES

1. THIS PROJECT WILL REQUIRE G.C. TO FILL OUT DAILY (ILSM) INTERIM LIFE SAFETY MANAGEMENT SHEETS.
2. ALL WORK AREAS UNDER CONSTRUCTION MUST BE SEALED OFF FROM ADJACENT AREAS.
3. NEGATIVE PRESSURE MUST BE MAINTAINED AT ALL TIMES IN CONSTRUCTION AREAS.
4. ALL DEBRIS LEAVING CONSTRUCTION AREAS FOR DUMPSTER MUST BE COVERED W/ DAMP COVER & CART WIPED DOWN PRIOR TO LEAVING.
5. CONTRACTOR TO MAINTAIN WET MAT, WALK-OFF MAT, BARRIER, & DRY MAT AT ALL CONSTRUCTION ENTRANCES.
6. WALK-OFF MATS TO BE CHANGED HOURLY MIN. OR AS NEEDED.
7. REFER TO TYP. ROOM LAYOUT DETAIL 10/A7.
8. G.C. TO INSTALL OWNER FURNISHED CONSTRUCTION SIGNAGE @ PATIENT ROOM ENTRY DOORS.

A Good Idea



Bid Documents




GENERAL NOTES:

- [illegible]

CONSTRUCTION DOCUMENTS

- Don't be intimidated
- Learn the jargon
- You are not expected to be an expert
- ASK QUESTIONS

CONSTRUCTION DOCUMENTS



PROJECT:
10100 / 10200 RENOVATION
Barnes Jewish Hospital South Campus
QUEENY TOWER / RAND JOHNSON - 10TH Floor

OWNER:
BARNES JEWISH Hospital
BJC HealthCare™

PROJECT TEAM

Owner
BJC HealthCare
9890 Clayton Road, Suite 100
St. Louis, MO 63124

Interior Design
The Lawrence Group Colors
319 N. 4th Street, Suite 1000
St. Louis, MO 63102

LIST OF DRAWINGS

Architectural

- AD-1 General Notes Sheet
- AD-2 Section Floor Plans
- AD-3 Floor Plans
- AD-4 Floor Section Plans
- AD-5 Floor Section Plans and Schedules
- AD-6 Construction Details
- AD-7 Construction Details
- AD-8 Construction Details
- AD-9 Construction Details
- AD-10 Construction Details
- AD-11 Construction Details
- AD-12 Construction Details
- AD-13 Construction Details
- AD-14 Construction Details
- AD-15 Construction Details
- AD-16 Construction Details
- AD-17 Construction Details
- AD-18 Construction Details
- AD-19 Construction Details
- AD-20 Construction Details

LOCATION PLAN

10th Floor
Queen Tower / Rand Johnson

Project I

12" Clear
See Plate
10-250

E-0	ELECTRICAL SPECIFICATIONS AND SYMBOLS
E-1	ELECTRICAL ONE-LINE DIAGRAMS
E-2	ELECTRICAL DEMOLITION PLAN
E-3	ELECTRICAL POWER PLAN NEW WORK
E-4	ELECTRICAL LIGHTING PLAN NEW WORK
E-5	ELECTRICAL PLAN - SYSTEMS

CONSTRUCTION PROCESS

- Now the fun begins
- IP needs to maintain high visibility
 - Minimally weekly rounds
- Barriers should be checked before project begins
- Demolition and drywall installation create the most dust
- What adjacent areas are impacted
- How much experience does this contractor have in hospitals
- How many phases is the project
- **Good communication**
- Weekly meeting attendance – ASK QUESTIONS

PRE-CONSTRUCTION RISK ASSESSMENT

- Determines potential hazards prior to start of project
 - Air quality
 - Utilities impact
 - Emergency preparedness
 - Fire/life safety – ILSM
 - Noise and vibration
 - IP requirements
 - Contractor Education



INTERIM LIFE SAFETY MEASURES

- Interim life safety measures (ILSM) were developed in response to an increase in fires in health care facilities due to high-risk construction activities
- ILSMs are put in place when construction activities impact the Life Safety Code (LSC)
- National Fire Protection Agency (NFPA) - ILSMs must be used when LSC impacted for >4 hours

Section I - General Information		
Project Name:		
Project Number:		
Project Summary:		
Facility:		
Location Within Facility:		
Project Start Date:		
Estimated Project Duration:		
Estimated Completion Date:		
Number of Phases:		
ILSM Evaluation Date:		
BJC Project Manager:		
BJC Project Manager Phone:		
BJC Project Manager Signature:		
Contractor:		
Contractor Project Manager:		
Contractor Project Manager Phone:		
Contractor Project Manager Signature:		
Project Safety Manager:		
Project Safety Manager Phone:		
Project Safety Manager Signature:		
Facility EH&S Representative:		
Facility EH&S Representative Phone:		
Facility EH&S Representative Signature:		
Facilities Manager:		
Facilities Manager Phone:		
Facilities Manager Signature:		
Infection Prevention Representative:	Loie Couch	
Infection Prevention Phone:	314-368-2064	
Infection Prevention Signature:		
Additional Signatures (may include: Department Manager, Project Superintendent, Subcontractors, Clinical Asset Management, IS, Security, Property Manager, etc.)		
Title	Name	Date
Note: Your signature will reflect approval of entire risk assessment package.		
If routed via email, routing slip is attached for verification of approval in place of actual signatures.		

Date:		
Project:	0	
Project Start Date:	10/19/00	
Location(Facility):	0	
BJC Project Manager:	0	
Contractor Project Manager:	0	
Instructions: For the designated BJC Project Manager (PM) to use as a tool to ensure that items are completed and/or exchanged as part of the risk assessment process.		
Y, N,	Item	
	Completed a Pre-Construction/Maintenance Risk Assessment.	
	Completed an ICRA.	
	Completed an ILSM, or determined N/A.	
	Completed a Construction and Demolition Environmental Checklist, or determined N/A.	
	Exchanged information on the control of hazardous energy sources (lockout/tagout).	
	Exchanged information on electrical safe work practices/Energized work documents.	
	Hot work activities to be performed/Hot work permits discussed.	
	Safety data sheets (availability/location discussed).	
	Required personal protective equipment on the job discussed/agreed.	
	Required environmental-related permits obtained.	
	Required Red tag permits discussed.	
	Additional:	
	Additional:	
	Project Manager exchanged any required information and provided appropriate documents/forms as applicable, on behalf of BJC and the specific facility.	
	Contractors received copies of the relevant core and site-specific policies and procedures.	
	Contractor and BJC site safety contact and emergency information exchanged.	
	Contractors agree to send copies of site safety walkthroughs to BJC Risk Management and the facility safety representatives upon request.	
Completed by:		
Type of Event	Code Name/Plain	Explanation of Code/Example
Fire	Code Red or Dr. Red	Include Location of fire.
Armed Violent Intruder	Code Silver	Include location of affected area NOTE: Plain language can be used for this event as well. If using plain language provide direction as well.
Bomb Threat	No Code or Broad Notification	Notification should be done to a smaller group and no code or overhead notification made. It is not typical to evacuate during a bomb threat.
Evacuation	Evacuation and Location	Evacuation - unit 9300
Hazardous Material	Hazardous Material Spill and	Hazardous Material Spill - room 2N80
Mass Casualty Event	Mass Casualty - Internal	Used for any patient surge due to internal emergency
	Mass Casualty - External	Used for any patient surge due to external emergency
	Mass Casualty - Decon	Used for any patient surge requiring chemical
	Mass Casualty - Radiation	Used for any patient surge involving radiation
Patient Abduction	Code Pink	Used for any pediatric patient but includes age of child and gender (i.e. Code Pink, 3 Male would be used for a three year old male) include location.
Security Code	Code White	Used to identify a potential aggressive situation or request for a response from a trained security team. NOTE: Plain language may be used for this event as well (see below)
Security Emergency	Security to (identify location)	Used for security emergency
Severe Weather	Activate Severe Weather Plan	

PRE-CONSTRUCTION/WORK RISK ASSESSMENT SUMMARY				
Classification:	<input checked="" type="checkbox"/> Construction	<input type="checkbox"/> Renovation	<input type="checkbox"/> Demolition	<input type="checkbox"/> Maintenance
Project Name:	14300 Schukar Patient Division Finishes		Facility:	BJH
Project Number:	2314001000		Location:	West Pavilion
Evaluation Date:	1/8/2024		Start Date:	2/6/2024
BJC Project Manager	Frank Diebold		Contractor:	BJH Facilities Construction
Project Summary	14300 Patient Unit Refresh-Finishes			
Describe the activities and tasks involved in the project.				
Category	Potential Hazards/Mitigation Strategies <small>(Examples listed below)</small>	Project Specific Mitigation Strategies <small>(Items do not apply, mark N/A in box)</small>		
Air Quality/Ventilation	Dust, fumes, mists, vapors, mold, product/task issues, location of makeup air, # of air changes, filter testing /maintenance. Assess need for monitoring.	Air/Dust controlled - hard partitions HEPA		
Blood borne Pathogens	Sharps containers, red bags.	N/A		
Barrier Management	Fire wall penetrations and holes (May require ILSM and/or permit).	To Facilities standards and inspection.ILSM and Permits to be posted		
Emergency Preparedness	Codes, contact lists, action plans identified/discussed.	Provided/ to be posted. Organizational correspondence distributed detailing project.		
Fire/Life Safety/ILSM	Hot-work, sprinkler/fire alarm shut-off (Red-tag permit), egress, signage.	All work coordinated with Building Maintenance staff.		
General Safety and Construction Safety hazards	PPE, fall protection (4' Rule), caught between, struck-by, ladder safety, within approach boundary of electrical equipment, etc.	PPE -safety glasses -safety toe boots. Ladder safety.		
Infection Prevention	Insert Risk Category and specific mitigation strategies per ICRA, attach barrier drawing.	ICRA Completed and posted. "Red" project. Patients are relocated to 5200 and 8900 during project.		
Hazardous Materials	Items from Environmental Concerns Checklist, cleaners, medical gases, oxygen, radiation, natural gas. Provide SDS for hazardous chemicals used.	All materials are -no VOC		
Mobile Equipment and Vehicle Operation	Emissions tier 3/4, assess need for spotters, flaggers, inspections, etc.	N/A		
Noise/Vibration	Power equipment, demolition, noise & vibration, assess need to monitor and plan to mitigate as required.	Some noise, Staff to be notified as work progresses.		
Utilities and Control of Energy Sources	Electrical access hazards, building impact, stored energy, lockout/tag out.	Any access to electric devices to be coordinated with Facilities.		
Special Hazards	MRI/Cryogen Safety, MRI quenching, chemical/biological/ radiological hoods/areas, radar scanner for embedded items	N/A		
Security	Access control, panic alarms, badges	Subs badged, access controlled		
Other	Contractor COVID Plan	1. Facemask properly donned when within Medical Center, 2. Social Distancing as often as possible >6', 3. Frequent hand washing, 4. Daily COVID-19 assessment check at entry portal before work start, 5. Daily assessment sticker placed on badge, readily visible.		
Instructions: Check categories for potential hazards and evaluate risks. Appropriate permits, procedures and forms will need to be implemented as part of the actions taken. November 2018				

Project Number:	0	Location:	0
Evaluation Date:	1/0/1900	Start Date:	1/0/1900
BJC Project Manager	0	Contractor:	0
Project Summary	0		
Describe the activities and tasks involved in the project.			
Category	Potential Hazards/Mitigation Strategies <small>(Examples listed below)</small>	Project Specific Mitigation Strategies <small>(Items do not apply, mark N/A in box)</small>	
Air Quality/Ventilation	Dust, fumes, mists, vapors, mold, product/task issues, location of makeup air, # of air changes, filter testing /maintenance. Assess need for monitoring.		
Bloodborne Pathogens	Sharps containers, red bags.		
Barrier Management	Fire wall penetrations and holes (May require ILSM and/or permit).		
Emergency Preparedness	Codes, contact lists, action plans identified/discussed.		
Fire/Life Safety/ILSM	Hot-work, sprinkler/fire alarm shut-off (Red-tag permit), egress, signage.		
General Safety and Construction Safety hazards	PPE, fall protection (4' Rule), caught between, struck-by, ladder safety, within approach boundary of electrical equipment, etc.		
Infection Prevention	Insert Risk Category and specific mitigation strategies per ICRA, attach barrier drawing.		
Hazardous Materials	Items from Environmental Concerns Checklist, cleaners, medical gases, oxygen, radiation, natural gas. Provide SDS for hazardous chemicals used.		
Mobile Equipment and Vehicle Operation	Emissions tier 3/4, assess need for spotters, flaggers, inspections, etc.		
Noise/Vibration	Power equipment, demolition, noise & vibration, assess need to monitor and plan to mitigate as required.		
Utilities and Control of Energy Sources	Electrical access hazards, building impact, stored energy, lockout/tagout.		
Special Hazards	MRI/Cryogen Safety, MRI quenching, chemical/biological/ radiological hoods/areas, radar scanner for embedded items		
Security	Access control, panic alarms, badges		
Other			
Instructions: Check categories for potential hazards and evaluate risks. Appropriate permits, procedures and forms will need to be implemented as part of the actions taken.			

Infection Control Risk Assessment (ICRA)

☒ Not Required for Project

Name of Project:	WUSH Ambulatory Center	Project #:	10104638
Location of Construction:	Through lobbies & pedestrian	Project Start Date:	1/29/2024
Phasing?:	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Is Heavy?:	Completion Date / Project End	1/29/2024 2/19/2024
Patient Relocation?:	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Contractor:	Clayco Construction
Relocation area:		IP Representative:	Luia Couch
Facility EHS Representative:	Emma Hankr	Facility Representative:	Shelly Brady

CONSTRUCTION ACTIVITY TYPES: Mark "X" in box next to type

<input type="checkbox"/>	Work Type A	Inspection and non-invasive activities, involving no dust, including but not limited to:
		<ul style="list-style-type: none"> Painting (but not sanding) Electrical trim work,, and activities which do not generate dust or require cutting of walls or access to ceiling other than for visual inspection
<input checked="" type="checkbox"/>	Work Type B	Small scale, short duration activities which create minimal dust, including but not limited to:
		<ul style="list-style-type: none"> Minor plumbing Removal of ceiling tiles for visual inspection Installation of telephone and computer cabling using existing "J" hooks or wire trays Removal of car-to-5 floor tiles or carpet squares Access to chaseways Cutting a small area of a wall where dust migration can be controlled such as within a closed chaseway or use of a hep vac while cutting
<input type="checkbox"/>	Work Type C	Typically large scale, longer duration activity (e.g. > one work shift) that generates a moderate to high level of dust, requires demolition or removal of any fixed building components or assemblies, including but not limited to:
		<ul style="list-style-type: none"> Sanding walls Removal > 5 floor tiles or carpet squares or removal of car work Any work above ceiling including J Hook or wire tray installation Major cabling activities Major demolition Wall covering or cave bare removal New construction

INFECTION CONTROL RISK GROUPS:

Mark "X" in box next to location. Using the following table, identify the patient risk group that will be affected. Consider impact on areas immediately above, below and or adjacent to the area where the active work is being performed.

Patient/Location Group 1-				Patient/Location Group 2-			
<input type="checkbox"/>	Outpatient clinics, excluding cancer clinics, transplant clinics and chemotherapy centers	<input type="checkbox"/>	All inpatient areas EXCEPT adult & pediatric oncology, and bone marrow transplant	<input type="checkbox"/>	Interventional Radiology/Pain Management Procedural Areas (Invasive Procedures)	<input type="checkbox"/>	All laboratory areas
<input type="checkbox"/>	Endoscopy suite	<input type="checkbox"/>	Emergency Department	<input type="checkbox"/>	Transplant unit, including Bone Marrow Transplant Unit	<input type="checkbox"/>	Special Care Nurseries (level 2 and 3)
<input type="checkbox"/>	Nuclear Medicine	<input type="checkbox"/>	Labor and Delivery	<input type="checkbox"/>	Central Sterile Processing	<input type="checkbox"/>	Dialysis Unit
<input type="checkbox"/>	Cardiology	<input type="checkbox"/>	Well baby nurseries	<input type="checkbox"/>	Operating Room (including C-section rooms)	<input type="checkbox"/>	Inpatient Oncology area
<input type="checkbox"/>	Pulmonary function lab	<input type="checkbox"/>	Pediatrics	<input type="checkbox"/>	Cancer clinics, including chemotherapy centers, transplant clinics	<input type="checkbox"/>	Pharmacy, main and all satellite
<input type="checkbox"/>	Echocardiography	<input type="checkbox"/>	Pre and post op areas	<input type="checkbox"/>	Radiation oncology/Gamma knife/Linear accelerator/Proton	<input type="checkbox"/>	Cardiac Cath Lab/Hybrid OR
<input type="checkbox"/>	Radiology/MRI, CT, PET/US	<input type="checkbox"/>	Pain Management Clinic	<input type="checkbox"/>	Intensive Care Unit	<input type="checkbox"/>	Laundry/Linen Room
<input type="checkbox"/>	Respiratory Therapy	<input type="checkbox"/>	Therapy Services			<input type="checkbox"/>	Outdoor work: <75 feet from an air intake
<input type="checkbox"/>	Wound center	<input type="checkbox"/>	Ultrasound				
<input type="checkbox"/>	Admitting	<input type="checkbox"/>	Main lobby areas and/or common hallways				
<input type="checkbox"/>	Offices (e.g. no patients present)	<input type="checkbox"/>	Medical Office Building/Doctors' offices				
<input type="checkbox"/>	EVS	<input type="checkbox"/>	Chapel				
<input type="checkbox"/>	Outdoor work: >75 feet from air	<input type="checkbox"/>	Kitchen, cafeteria				

Construction Activity					
Risk Level	Year 0 (as built)		Year 1 (minimal dust)		Year 2 (moderate / major dust)
Grade 1 -	<input type="checkbox"/>	GREEN	<input type="checkbox"/>	YELLOW	<input type="checkbox"/>
Grade 2 -	<input type="checkbox"/>	GREEN	<input type="checkbox"/>	RED	<input type="checkbox"/>
Grade 3 -	<input type="checkbox"/>	GREEN	<input type="checkbox"/>	RED	<input type="checkbox"/>
Job Class		DURING Construction Project			
GREEN	Check if applicable	MP #	Interventions:	Additional Notes	
No dust, nuisance	<input checked="" type="checkbox"/>		Clear doors to patient rooms or offices near work		
	<input checked="" type="checkbox"/>		Doors closed to supply areas or areas where supplies likely; store supplies away from where work is performed		
	<input checked="" type="checkbox"/>		Linen carts covered or moved away from where work is performed		
	<input checked="" type="checkbox"/>		Cover office furniture, monitors and equipment with plastic; protect personal belongings as appropriate		
	<input checked="" type="checkbox"/>		Additional requirements not already documented:		
YELLOW	Check if applicable	MP #	Interventions:	Additional Notes	
Additional to Green above Control of dust	<input checked="" type="checkbox"/>		Infection Prevention Specialist consulted at least 3 business days (72 hrs) prior to start of project.		
	<input checked="" type="checkbox"/>		Post signage at beginning of project if project is less than 24 hours; Responsible person: _____		
	<input checked="" type="checkbox"/>		Project supervisor and HSO specify facility workers to check in with department manager or designer (e.g. change rooms) at the beginning of each shift: _____ Change rooms _____ Department / Office manager _____ Other (specify) _____		
	<input checked="" type="checkbox"/>		Use methods to minimize migration of dust, other contaminants and/or accumulation of water, such as working within a suite, misting of ceiling surface with water (with or without bleach), appropriate plastic barriers, use of kerosene while mopping, etc.		
	<input checked="" type="checkbox"/>		Mist mop floor before removal		
	<input checked="" type="checkbox"/>		No patients present in entire work area		
	<input checked="" type="checkbox"/>		Materials being brought to project site should be covered/wrapped		
	<input checked="" type="checkbox"/>		Debris removed in covered containers		
	<input checked="" type="checkbox"/>		Designate an elevator or route for debris removal when necessary		
	<input checked="" type="checkbox"/>		Open penetrations must be covered if unattended (e.g. plastic, dry wall, etc)		
	<input checked="" type="checkbox"/>		Access points without barriers must be closed if unattended		
	<input checked="" type="checkbox"/>		Ceiling tiles replaced ASAP and must be closed if unattended		
	<input checked="" type="checkbox"/>		Walk off sticky mats		
	<input checked="" type="checkbox"/>		Clean work site at end of workday.		
	<input checked="" type="checkbox"/>		HEPA machine in area as air scrubber. Designate location of machine: _____	any work done during the day will be leaving HEPA filters. At night it will be in public areas when calling for the service	
<input checked="" type="checkbox"/>		Additional requirements not already documented:			

Check if applicable	MP #	Interventions:	
<input type="checkbox"/>		Patients in near rooms when entering or leaving HSO.	
<input type="checkbox"/>		Multifunction responsibility person: IP Other (Specify)	
<input type="checkbox"/>		Barriers unattended and inspected by IP prior to beginning work	
<input type="checkbox"/>		Barrier type: Air tight wall (plastic) wall (unacceptable if work lasts 72-96 hrs or less per direction of IP/SAFEQ); Air tight hard wall partition (floor to desk); Air tight hard wall partition (floor to ceiling) with wall (plastic) wall (ceiling to desk)	
<input type="checkbox"/>		Ceiling plastic curtain required	
<input type="checkbox"/>		Barrier seams taped	
<input type="checkbox"/>		Maintain negative air flow within containment site (Hole: up off air supply if necessary to achieve negative pressure)	
<input type="checkbox"/>		Check pre filters on fans or units used to maintain negative air flow (annually HEPA) at least daily or more frequently if major demolition	
<input type="checkbox"/>		Use minimal monitor/side for negative air pressure.	
<input type="checkbox"/>		Contractor to document at least daily that negative pressure is being maintained.	
<input type="checkbox"/>		Return air units blocked or sealed before beginning work if applicable.	
<input type="checkbox"/>		Monitor and change return unit filters as needed and document.	
<input type="checkbox"/>		Workers to remove dust from clothing prior to entering any hospital area; e.g. sticky mats, vacuum clothing, apply clean clothing or remove coveralls and shoe coverings	
<input type="checkbox"/>		When going thru ventilation area, protective attire (PA) must be worn in access entrance and work area. PA must be removed before entering the work area because it will be used again to exit	
<input type="checkbox"/>		Keep work area clean e.g. wet mop or HEPA vac frequently X per day to decrease risk of tracking dust through clean areas	
<input type="checkbox"/>		Wet mop (mop consider 10X bleach solution); If using both sticky mats and wet mop, order should be wet mop, dry mop, sticky mat	
<input type="checkbox"/>		Create an air room (ORs, kennel/BHT units, large areas where negative pressure difficult to achieve, etc)	
<input type="checkbox"/>		Mist outdoor containment site frequently and as needed to prevent dust accumulation	
<input type="checkbox"/>		Wet mop cement	
<input type="checkbox"/>		Avoid location of air intakes for outdoor projects and/or projects where work is being done < 75 ft from intakes; additional or higher filtration may be required to avoid entry of contamination (e.g. dust and debris) of air intakes	
<input type="checkbox"/>		Partner with EH&S to determine if air sampling (e.g. particle counts) is required during the project.	
<input type="checkbox"/>		Additional requirements not already documented:	

ICRA

- Completed for each project
- May need one for each phase
 - Patient proximity and intensity of work determines precautions
- Reviewed with contractors and project manager
- Barriers should be evaluated prior to work beginning and throughout the project

ICRA

- Type of Barriers
- Project entrance and exit
- Path for debris hauling and equipment hauling
- Elevator use
 - Limited hours of use
- Placement of sticky mats
- Hours of work
- Contact information if work needs to be stopped

ICRA

- Weekly walkthrough with super
- Head laborer
- Different trades on site
- Familiarity with contractors

OTHER CONSTRUCTION SAFETY ISSUES

- How work permit
- Fire watch
- Electrical safety – lock out tag out
- Indoor air quality
- Confined work space
- Barrier access permits – maintaining fire and smoke compartments

BARRIER ACCESS PERMITS

- Above ceiling permit
- Required by Joint Commission
- Assures integrity of fire stopping above ceiling is maintained
- Must have gone through IP training to obtain permit
- Will be displayed at jobsite
- Electricians usually display on ladder


NOW THE FUN BEGINS

- Make yourself visible and reachable
- Make sure contractors understand your expectations
 - Contractor safety class
- Make time for project walk throughs
- Frequency determined by several factors
 - Contractors time on campus
 - History with contractor previous good and or bad experiences)
 - High risk areas
- Ask questions
- Good communication

WHAT TO LOOK FOR



















CONSTRUCTION IS FINISHED

- Commissioning
- All systems operating as designed
 - Testing done prior to demolition for comparison
- Hand sanitizer and sharps appropriately placed

CONSTRUCTION IS FINISHED

- Area cleaned by contractor
- Area cleaned by EVS
- All water sources run to make sure no stagnant water
- Work with moving team to get patients back to unit
- Unit opens with patients



DON'T FORGET

- Your crew of in-house guys
- Planned maintenance
- Every system in the hospital
 - Electrical
 - Plumbing
 - HVAC
 - Fire protection
- Minor emergent issues

FACILITIES ENGINEERING

- Infrastructure failures
 - Daily issues
 - Urgent – emergent issues
- ICRA for repairs









QUESTIONS?

- Loie Couch, RN, BS, CIC, FAPIC
- loie.couch@bjc.org
- 314-368-2064

